

GUJARAT TECHNOLOGICAL UNIVERSITY
Diploma Engineering - SEMESTER-VI • EXAMINATION – SUMMER 2013

Subject Code: 365004**Date: 09/05/2013****Subject Name: Estimating and Costing****Time: 10:30 am TO 01:00 pm****Total Marks: 70****Instructions:**

1. Attempt all questions.
2. Make suitable assumptions wherever necessary.
3. Figures to the right indicate full marks.
4. English version is considered to be Authentic.

- Q.1** (a) Explain the types of Approximate Estimate. Explain in detail any one of it. **07**
 (b) Give the Service Unit for the following **07**
 1) Bridge 2) School 3) Canal 4) Dam 5) Hospital 6) Jail 7) Water Tank
- Q.2** (a) Write the unit of measurement for the following: **07**
 1. Wooden Door Frame and Shutter 2. C.I. Man Hole Cover
 3. Wire Fencing 4. Tile Flooring
 5. DPC(30mm Thick) 6. Cement Pointing
 7. R.C.C. Stair
- (b) Write short note on (Any two): **07**
 1. Administrative Approval
 2. Prime Cost and Provisional Sum
 3. Bar Bending Schedule
- OR**
- Q.3** (b) State the qualities of “Good Estimator” **07**
 (a) Define Rate Analysis and State the Factors affecting rate analysis **07**
 (b) What is Task Work ? State the factors affecting Task Work **07**
- OR**
- Q.3** (a) What is S.O.R.? Why it is periodically revised ? **07**
 (b) Write Short Note (Any Two): **07**
 1. Work Charged Establishment
 2. Technical Sanction and 3. Spot Item
- Q.4** (a) Derive Rate Analysis for “First Class Brick Work In C.M. (1:6) for Super Structure **07**
 (b) Work out the quantities for the following Items for the R.C.C. Slab from the given drawing Fig- 1 **07**
 (1) Find out quantity of concrete for “Slab”
 (2) Find out weight of main steel for slab
- OR**
- Q.4** (a) Derive Rate Analysis for “12mm thick Cement Plaster in C.M. (1:6)” **07**
 (b) Work out the quantities for the following item for the R.C.C. Slab from the given Drawing Fig-1 **07**
 (1) Find quantity of Form Work for Slab
 (2) Find weight of Steel for Distribution Bar for Slab
- Q.5** Work out the quantities for the following Items for the building drawing shown in fig 2: **14**
 1. Excavation for foundation
 2. Brick work In C.M.(1:6) for super structure
- OR**
- Q.5** Work out the quantities for the following Items for the building drawing shown in fig 2: **14**
 1. B.B.L.C. (1:4:8) for foundation
 2. Brick Masonry (1:6) for Foundation and up to Plinth

- Q.1** બા અંદાજીત અંદાજના પ્રકારો જણાવો.તેમાંથી ગમે તે એકને વિગતવાર સમજાવો. ૦૭
- ખ નીચેના માટે અંદાજીત અંદાજના સર્વિસ એકમો જણાવો. ૦૭
- (1)બ્રીજ(2).સ્કૂલ (3) કેનાલ (4) ડેમ (5) હોસ્પિટલ (6) જેલ
(7) પાણી ની ટાંકી
- Q.2** બા નીચેની વિગતોના માપણીના એકમો લખો ૦૭
- ૮૫૯ બારણા ની ફેમ અને શટર (2.)સી.આઇ. મેનહોલ કવર
(3)વાયર ફેન્સીંગ (4) ટાઇલ્સ ફ્લોરીંગ
(5) ડી.પી.સી.(30મી.મી.જાડી)(6) પોઇન્ટીંગ
(7) આર.સી.સી.પગથીયા
- ખ ટ્રેક નોંધ લખો(ગમે તે બે) ૦૭
- (1)વહીવટી મંજૂરી (2) પ્રાઇમ કોસ્ટ અને પ્રોવીઝનલ સમ
(3)બાર બેન્ડીંગ શીડયુલ
- અથવા
- B સારા અંદાજકાર ના ગુણો જણાવો. ૦૭
- Q.3** બા ભાવ પૃથ્થકરણ ની વ્યાખ્યા આપો.ભાવ પૃથ્થકરણને અસર કરતા પરીબળો જણાવો. ૦૭
- ખ “ટાસ્ક વર્ક” એટલે શું?તેને અસર કરતા પરીબળો જણાવો. ૦૭
- અથવા
- Q.3** બા એસ.ઓ.આર.એટલે શું ? તે સમયાંતરે શા માટે સુધારાય છે? ૦૭
- ખ ટ્રેક નોંધ લખો (ગમેતે બે) ૦૭
- (1.)વર્કચાર્જ એસ્ટાબ્લીશમેન્ટ (2) તાંત્રિક મંજૂરી (3) સ્પોટ આઇટમ
- Q.4** બા નીચેના માટે ભાવ પૃથ્થકરણ કરો. ૦૭
- સુપર સ્ટ્રકચર માટે પ્રથમ કક્ષાની ઇંટનું 1:6 ના સિમેન્ટ કોલ માં ચણતરકામ.
- ખ આકૃતિ-1 માં દર્શાવેલ આર.સી.સી. સ્લેબ માટે નીચેની રાશિ શોધો. ૦૭
- (1.)સ્લેબ માં વપરાયેલ કોન્ક્રીટના જથ્થાની રાશિ
(2)સ્લેબમાં વપરાયેલ મુખ્ય સળિયાનું વજન શોધો.
- અથવા
- Q.4** બા નીચેના માટે ભાવ પૃથ્થકરણ કરો. ૦૭
- 12 મી.મી.જાડું સિમેન્ટ પ્લાસ્ટર 1:4ના સિમેન્ટ કોલ માં
- ખ આકૃતિ:1 માં દર્શાવેલ આર.સી.સી. સ્લેબ માટે નીચેની રાશી શોધો. ૦૭
- ૮૫૯ સ્લેબમાં વપરાયેલ ફોર્મવર્કની રાશી .

Q.5

સ્લેબમાં વપરાયેલ ડીસ્ટ્રીબ્યુશન સળિયાનું કુલવજન
આકૃતિ:2 માં દર્શાવેલ બિલ્ડીંગ સ્ટ્રક્ચર માટે નીચેની રાશી શોધો
(1)પાયા ના ખોદાણકામ ની રાશી
(2)સુપર સ્ટ્રક્ચરમાટે 1:6 ના સિમેન્ટકોલમાં ઇંટનું ચણતરકામ
અથવા

૧૪

Q.5

આકૃતિ:2 માં દર્શાવેલ બિલ્ડીંગ સ્ટ્રક્ચર માટે નીચેની રાશી શોધો.
(1)બી.બી.એલ. સી. (1:4:8) ફોર ફાઉન્ડેશન ની રાશી
(2)પાયા અને પ્લીન્થ સુધીના ઇંટનું ચણતરકામ 1:6 ના સિમેન્ટ કોલની
રાશી નો જથ્થો.

૧૪






Fig-2



All Walls are of same section
Lintel over Doors. Windows and
Shelves are 15 cm thick R.C.

Doors D-1.50 m x 2.10 m
Windows W-1.50 m x 1.50 m
Shelves S-1.50 m x 1.50 m

Fig. 2-B